		Mtrs	5	30.00			150.00	165.00	24750.00
	Labour charges for laying 1.1 KV class UG cable when supplied by agencies in existing trenches GI pipe / stoneware pipe/ on pole as required, P-427, I-11 (a), B SSB SR 2012-13.								
		Mtrs	5	30.00			150.00	5.50	825.00
28	Digging of trench of 0.6m deep x 0.5m wide refilling the trench to the required level and consolidating etc., complete P-427, I-12 (a), BWSSB SR2012-13.								
		Mtrs	5	15.00			75.00	44.00	3300.00
29	Supply and fixing LT cast iron pot heads suitable for 1.1 KV class 16 sqmm UG cable filled with neccesary bitumen / insulating compound complete with termiinalas, clamps, bolts, nuts, washers etc., P-428, I-16(b), BWSSB SR 2012-13.								
		Nos	5				5.00	264.00	1320.00
30	Supplying and fixing of porcelain fuse channel with cut-out on existing / new wooden panel using neccesary nuts, bolts and washers etc., BWSSB SR P-394 I-173								
		Nos	5	6.00			30.00	440.00	13200.00
31	BESCOM Deposit charge and miscellanious.	L.S	5			L.S	5.00	15000.00	75000.00
32	Cutting of road surface for pipeline trenches and disposing of the excavated stuff as directed including barricading, danger lighting etc., in the Asphalt surface road. (Pg. No-272, I.No-37.38) PWD SR 2013-14								
		Cum	5	185.00	0.60	0.15	83.25	253.00	21062.00
33	Earthwork excavation for foundation of buildings water supply, sanitary lines and electrical conduits either in pits or in trenches 1.5m and above in width, in hard soil not exceeding 1.5 m. in depth including dressing the bottom and sides of pits and trenches, stacking the excavated soil clear from edges of excavation with lead upto 50 m. after breaking of clods complete as per specifications. specification. Noll KBS 2.1.C/2.9.4/2.18/2.19 (Pg. No-05, I.No-2.4) PWD SR 2013-14								
		Cum	5	185.00	0.60	0.75	416.25	227.88	94855.00
34	Providing and installing at site of work P.V.C pipees including cost of pipes and specials and labour including lowering into trenches, laying true to line, level and perfect linking at joints leak proof including jointing of approved type with all labour and lift charges, handling charges including encasing the pipe alround to a depth not leass than 15 cms with gravel or selected earth available from the excavation etc., complete PVC pipes of 6kg/Sqm 75mm Dia.(Page NO-102, iTEM no-13.15 (b), of PRED SR 2012-13).								
		Rmt	5	~~185.00~~ 273.00			~~925.00~~ 1365.00	~~157.00~~ 117.00	~~145225.00~~ 159705.00
35	Supplying and fixing 50 mm GI pipes 'B' class heavy duty (As PER bwssb Store Issued Rate) **Note:**- GI Pipe using for Road crossing places.								
		Mtrs	5	10.00			50.00	325.00	16250.00
36	Refilling available earth around pipe lines, cables in layers not exceeding 20cms in depth, compacting each deposited layer by ramming after watering with lead upto 50m. and lift upto 1.5m. Including cost of all labour complete as per specification. (Pg. No-6, I.No-2.11 PWD SR 2013-14).)								
		Cum					416.25	60.48	25175.00
37	Transportation of pumping machineries PRE SR 2012-13 PG 56/10.3.19						5.00	900.00	4500.00